THE CITY OF TEA TREE GULLY

› Technical Specifications

WAYFINDING

DESCRIPTION: FACILITIES, PARKS & RESERVES - GROUND MOUNT

CODE: WAY11 12/08/2025

APPLICATIONS

Regional	●
District	●
Neighbourhood	●
Local	●
Main Roads	○
Local Roads	○

PERFORMANCE CRITERIA	high legibility, minimal maintenance, does not create hazards for users, visually appealing, suitable for outdoors, vandalism resistant

IMAGE/S

Images are indicative of the style, not a specific brand. Council's procurement policy must be followed when selecting and purchasing items.



CITY OF TEA TREE GULLY

MATERIALS	Sign: 8mm mild steel plate (part No. 2325_TTG_05_A_401) x 1 Footing Template (part No. 2325_TTG_05_A_403) x 1 M16 Security Nut x 8 Anchorage Assembly: (part No. 2325_TTG_700) x 2
FINISHES	2-PAC spray to match PMS Black7, gloss UV Digital Print UV Clear Coat
COLOURS	Base Colour - Warm Grey CYMK: 63,57,58,63 / RGB: 53,52,51 / #353433 Orange - 166CP CMYK: 0,77,100,0 / RGB: 242,99,34 / #f26332 Blue - 299C CMYK: 74,21,0,0 / RGB: 0,161,223 / #00A1DF
SIZE (INDICATIVE)	Fabricated: W1703.8mm x H1000mm
VARIATIONS	Orange - Parks & Reserves Blue - Facilities
OPTIONS	
INSTALLATION INSTRUCTIONS	Remove all flash, burrs and sharp edges All welds to be 6mm continuous fillet all round (category GP), unless noted otherwise, in accordance with AS1554 450 x 800mm poured concrete footings 3mm plate 4 N 12 vertical bars with W6-300 centre ligatures. Minimum 100mm edge distance
MAINTENANCE	Reactive
EXPECTED LIFESPAN / END OF LIFE REPLACEMENT	10 years
RELEVANT STANDARDS	To be read in conjunction with engineering report reference No: 2012-1800TT Drawings: 2325_TTG_05_A_400 / 2325_TTG_05_A_401 / 2325_TTG_05_A_403



CITY OF
TEA TREE GULLY